

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division

Scheudle - B

NAME OF THE WORK: Improvements to roads and drains at Vijaya lakshmi layout and bagalagunte in Bagalagunte ward no. 14 Dasarahalli sub division

Sl. No	Description of work	Unit	Qty	Rate Quoted by Sri. N.Shivananda	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3 (P.142/I.19.1 PW, P & IWTD -SR 2016-17)	Cum	153.78	75.0	Rupees Seventy Five Only
2	Removing B.S.Slab of drain and stacking etc., complete Page No. 25/ Item No. 5.32/ PWD SR 2016-17	Sqm	251.64	58.0	Rupees Fifty Eight Only
3	KSRRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.3) PWD - SR 2016-17)	Cum	80.39	4800.0	Rupees Four Thousand Eight Hundred Only
4	KSRRB 4-1.6: Providing and laying in position plain cement concrete of mix M1:2:4 with cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.6) PW, P & IWTD - SR 2016-17)	Cum	44.27	5200.0	Rupees Five Thousand Two Hundred Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

BBMP

5	Refixing stone slabs of drains and pointing in CM 1:3 etc complete Page No. 25/ Item No.5.33/ PWD SR 2016-17	Sqm	251.64	65.0	Rupees Sixty Five Only
6	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 thick (P. 25 I. 5.31.1) Page No. 25/ Item No. 5.31.1/ PWD SR 2016-17	Sqm	167.76	650.0	Rupees Six Hundred Fifty Only
7	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No. 25/ Item No. 5.27/ PWD SR 2016-17	Sqm	366.40	950.0	Rupees Nine Hundred Fifty Only
8	Supplying and fixing precast reinforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm	419.40	1600.0	Rupees One Thousand Six Hundred Only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Page No. 133 Item No. 17.1 PWD SR 2016-17	Cum	153.78	75.0	Rupees Seventy Five Only


Signature of the Contractor


Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer
Dasarahalli Division